



SUMMARY TEST REPORT

FOR: Andersen Corporation
 100 Fourth Avenue North
 Bayport, MN 55003

Report Number: C9043.03-201-47
 Test End Date: 05/30/2013
 Report Date: 07/10/2013
 Test Record Retention End Date: 07/10/2017

SERIES TESTED: 100 Series Transom
 MODEL TESTED: 100TR8020 IG

NAFS-08/-11 Class LC-PG30 Size Tested 95.3 x 23.3 in. DP+30/-30
NAFS-05 N/A

<u>Test</u>	<u>Results Summary</u>
Operating Ease	N/A
Resistance to Air Infiltration	0.01 cfm/ft ² (ASTM E283)
Resistance to Water Penetration	Pass at DP30 (ASTM E547)
Resistance to Structural Loading	Pass at DP30 (ASTM E330)
Forced Entry Resistance	Pass (ASTM F 588)

CAN/CSA A440-00, Evaluation to the prescriptive requirements were not performed

<u>Test</u>	<u>Rating</u>
Operating Ease	N/A
Air Tightness	Fixed
Water Tightness	B2
Wind Load Resistance	C2
Blow-Out	C2

<u>Test</u>	<u>Results Summary</u>
Impact	(N/A)
Pressure Cycling	(N/A)

REFERENCE:	See ATI Report No. C9043.01-201-47 and C9043.02-201-47 for complete test results
-------------------	----------------------------------------------------------------------------------

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

ARCHITECTURAL TESTING, INC

ARCHITECTURAL TESTING, INC

Karl A. Lips-Eakins
 Senior Technician

Daniel A. Johnson
 Director of Regional Operations

849 Western Avenue North
 St. Paul, MN 55117
 Phone: 651-636-3835
 Fax: 717-764-4129
 www.archtest.com